

2012 Additional Block E Soil Investigation Report Lockheed Martin Middle River Complex 2323 Eastern Boulevard Middle River, Maryland

Prepared for:

Lockheed Martin Corporation

Prepared by:

Tetra Tech, Inc.

December 2012



Michael Martin, P.G.
Regional Manager



Dev Murali, P.G.
Project Manager

ACRONYMS

As	arsenic
AST	aboveground storage tank
ATC	anticipated typical concentration
BaPEq	benzo(a)pyrene equivalent
bgs	below ground surface
BTEX	benzene, toluene, ethyl benzene, and xylenes
CCTV	closed-circuit television
COC	contaminant(s) of concern
COPC	contaminant(s) of potential concern
CrVI	hexavalent chromium
CSM	conceptual site model
14-DCB	1,4-dichlorobenzene
DNAPL	dense non-aqueous-phase liquids
DPT	direct-push technology
DRO	diesel-range organics
EDD	electronic data deliverable(s)
EESH	energy, environment, safety, and health
EGIS	environmental geographic information system
ERI	electrical resistivity imaging
ESA	environmental site assessment
ft/d	feet per day
GIS	geographic information system
g/d/ft	gallon(s) per day per foot
gpm	gallon(s) per minute
GPR	ground-penetrating radar
GPS	global positioning system
GRO	gasoline-range organics
HASP	health and safety plan
HHRA	human health risk assessment
HI	hazard index
ILCR	incremental lifetime cancer risk
IDW	investigation-derived waste
IRM	interim remedial measures

kip	kilopound
LMCPI	Lockheed Martin Corporation Properties, Inc.
LNAPL	light non-aqueous phase liquid
Lockheed Martin	Lockheed Martin Corporation
MDE	Maryland Department of the Environment
µg/kg	microgram(s) per kilogram
µg/L	microgram(s) per liter
mg/kg	milligram(s) per kilogram
MRAS	Middle River Aircraft Systems
MRC	Middle River Complex
MS2—S&AS	Mission Systems & Sensors—Ships & Aviation Systems
msl	mean sea level
NPDES	National Pollutant Discharge Elimination System
PAH	polycyclic aromatic hydrocarbon
PCB	polychlorinated biphenyl
pCi/g	picocurie(s) per gram
PDF	portable document format
PID	photoionization detector
PM	project manager
PPE	personal protective equipment
ppm	part(s) per million
REC	recognized environmental condition
RSL	regional screening level
SVOC	semivolatile organic compound
123-TCB	1,2,3-trichlorobenzene
124-TCB	1,2,4-trichlorobenzene
TCE	trichloroethene
Tetra Tech	Tetra Tech, Inc.
t-PCB	total polychlorinated biphenyl
TPH	total petroleum hydrocarbon
TSCA	Toxic Substances Control Act
UCC	utility cross-connection
USCS	Unified Soil Classification System
USDA	United States Department of Agriculture
USDOT	United States Department of Transportation
USEPA	United States Environmental Protection Agency
UST	underground storage tanks

VC vinyl chloride
VOC volatile organic compound

This page intentionally left blank

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
ACRONYMS	vii
1 INTRODUCTION	1-1
2 SITE BACKGROUND	2-1
2.1 MIDDLE RIVER COMPLEX BACKGROUND.....	2-1
2.1.1 Location	2-1
2.1.2 History and Operations	2-1
2.1.3 Surrounding Land Use	2-2
2.1.4 Physiography.....	2-2
2.1.5 Soils.....	2-2
2.1.6 Hydrology	2-3
2.1.7 Geology.....	2-3
2.1.8 Hydrogeology	2-5
2.2 BLOCK E SITE CHARACTERISTICS.....	2-7
2.2.1 History and Operations	2-7
2.2.2 Block E Reconnized Environmental Conditions and Contaminants of Concern	2-7
2.3 SUMMARY OF BLOCK E INVESTIGATIONS	2-8
2.3.1 Phase I Environmental Site Assessment (Winter 2003).....	2-10
2.3.2 Phase II Site Investigation of Exterior Areas (Fall/Winter 2003).....	2-10
2.3.3 Radiological Survey of Former Building D (REC #1) (Winter 2004).....	2-11
2.3.4 Site-Wide Phase II Investigation (2004).....	2-12
2.3.5 Phase II Soil Investigation (Summer 2005)	2-13
2.3.6 Site Characterization Report (May 2006).....	2-13
2.3.7 Additional Field Investigation (Fall 2007)	2-14
2.3.8 Supplemental Soil and Storm Drain Sediment Characterization Report (Fall 2008).....	2-15
2.3.9 Data Gap Investigation (Fall 2010).....	2-16
2.3.10 Human Health Risk Assessment for Soil (Spring 2011).....	2-17
2.3.11 Additional Soil Investigation (July–August 2011)	2-20
2.3.12 Human Health Risk Assessment Update (Fall 2011).....	2-22
2.3.13 Utility Cross-Connection Study (Summer 2011).....	2-24

TABLE OF CONTENTS (continued)

<u>Section</u>	<u>Page</u>
2.3.14 Block E Storm-Drain Interim Remedial Measures (Fall 2011)	2-26
2.3.15 Pilot Injection Program (Fall 2011)	2-28
2.3.16 Blocks E and G Pre-Design Soil Sampling Investigation (Summer 2012)	2-29
3 INVESTIGATION APPROACH AND METHODOLOGY	3-1
3.1 MOBILIZATION/DEMOBILIZATION	3-2
3.2 SUBSURFACE ELECTRICAL RESISTIVITY IMAGING	3-4
3.3 CONCRETE SAMPLING	3-4
3.4 SOIL SAMPLING	3-5
3.4.1 Peripheral Shallow Soil Sampling	3-5
3.4.2 Deep Soil Sampling	3-6
3.5 GROUNDWATER LEVELS AND SAMPLING	3-7
3.6 SAMPLE NOMENCLATURE	3-8
3.7 SAMPLE HANDLING	3-8
3.8 DOCUMENTATION	3-9
3.9 LABORATORY ANALYSES	3-9
3.10 SURVEYING	3-10
3.11 EQUIPMENT DECONTAMINATION	3-10
3.12 WASTE MANAGEMENT	3-10
3.13 DATA VALIDATION	3-10
3.14 DATA MANAGEMENT	3-12
3.14.1 Data Tracking and Control	3-12
3.14.2 Sampling Information	3-13
3.14.3 Project Data Compilation	3-13
3.14.4 Geographical Information System	3-13
4 RESULTS	4-1
4.1 GEOPHYSICAL SURVEY	4-1
4.2 GROUNDWATER LEVELS	4-2
4.3 CONCRETE,	ADR.(O)7]6t(m)-2(wO.-2(wU)2(R)7M)13(N)2(A)112(T)-9*(.)-2(
4.3 CONCRETE,.....4(V)-8(E)-9(L3L)21Am.....	4-2

TABLE OF CONTENTS (continued)

Section	Page
4.4 GROUNDWATER SAMPLING.....	4-11
4.5 POLYCHLORINATED BIPHENYLS.....	4-13
4.5.1 Eastern Storm Drain Manholes and REC #3 - Former 500,000-Gallon AST and Associated Tanks	4-11
4.5.2 Former Milling/Plating/Finishing Area and South-Central Former Transformer Room.....	4-12
4.5.3 Former Waste Disposal Area and Southwestern Former Transformer Room....	4-12
4.6 BENZO(A)PYRENE EQUIVALENTS.....	4-13
4.7 TOTAL PETROLEUM HYDROCARBONS	4-14
5 BLOCK E SOUTHWESTERN AREA CONCEPTUAL SITE MODEL FOR POLYCHLORINATED BIPHENYLS	5-1
5.1 BLOCK E FORMER SITE OPERATIONS	5-2
5.2 BLOCK E CONCRETE SLAB FOUNDATION	5-3
5.3 BLOCK E GEOLOGY AND HYDROGEOLOGY	5-4
5.4 BLOCK E SURFACE WATER.....	5-6
5.5 BLOCK E POSSIBLE PCB-RELEASE MECHANISMS AND TRANSPORT PATHWAYS	5-7
6 SUMMARY	6-1
7 REFERENCES.....	7-1

APPENDICES

**APPENDIX A—RADIOLOGICAL SCREENING AND SAMPLING REPORT AND
WORK PLAN**

APPENDIX B—UTILITY CLEARANCE REPORT

APPENDIX C—AESTUS GEOPHYSICAL SURVEY REPORT

APPENDIX D—SOIL BORING LOGS

APPENDIX E—SAMPLE RECORD SHEETS

APPENDIX F—DATA VALIDATION REPORTS

APPENDIX G—SURVEY REPORT

TABLE OF CONTENTS (continued)

APPENDIX H—CHEMICAL DATA TABLES

APPENDIX I—HISTORICAL DRAWINGS

APPENDIX J—INVESTIGATION-DERIVED WASTE

LIST OF FIGURES

	<u>Page</u>
Figure 1-1	Middle River Complex Location Map 1-4
Figure 2-1	Middle River Complex Site Layout and Tax Blocks 2-36
Figure 2-2	Geologic Cross-Section Locations 2-37
Figure 2-3	Geologic Cross-Section A–A' 2-38
Figure 2-4	Geologic Cross-Section B–B' 2-39
Figure 2-5	Geologic Cross-Section C–C' 2-40
Figure 2-6	Aerial Photograph of Former Building D—1944 2-41
Figure 2-7	Factory Layout of Former Building D Basement 2-42
Figure 2-8	Historical Exceedances of PCB and BaPEq Residential Use Screening Levels through 2010 2-43
Figure 2-9	PCB Results in Block E Soil Samples Exceeding the Residential Use Screening Level—July and August 2011 2-44
Figure 2-10	Block E Pre-Design Soil-Sample Residential-Use Screening Level Exceedances 2-45
Figure 3-1	Block E 2012 Geophysical Survey Transect Locations 3-32
Figure 3-2	Block E 2012 Concrete Sampling Locations 3-33
Figure 3-3	Block E 2012 Peripheral Shallow Soil Boring Locations 3-34
Figure 3-4	Block E 2012 Deep Soil Boring Locations 3-35
Figure 4-1	Block E Groundwater Elevation Contour Map—Upper Surficial Aquifer, July 2012 4-73
Figure 4-2	PCBs Detected in 2012 Block E Concrete Samples at Locations with Historical PCB Results 4-74
Figure 4-3	PCBs Detected in June–July 2012 Block E Concrete and Soil Samples at Locations with Historical PCB Results 4-75
Figure 4-4	BaPEq Detected in June–July 2012 Block E Soil Samples at Locations with Historical BaPEq Results 4-76
Figure 4-5	TPH Detected in June–July 2012 Block E Soil Samples at Locations with Historical TPH Results 4-77

